Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.
Schedule - B

Name of the Work : Construction of RCC drain in 22nd, 23rd and other cross roads at Ravindra Nagar in ward no. 13 in Shettyhalli sub division

SNo	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Kumara BJ	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of engineer in charge of the work	Cum	668.90	180.00	Rupees One Hundred and Eighty Only
2	Removing B S Slab Drain And Stacking etc complete as per specifications and directions of engineer in charge of the work	sqm	845.10	70.00	Rupees Seventy Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work **From Using Available coarse aggregates**	Cum	74.57	4450.00	Rupees Four Thousand and Four Hundred and Fifty Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work	Cum	19.33	5300.00	Rupees Five Thousand and Three Hundred Only

Signature of the Contractor

EXECUTIVE ENGINEER
Executive Engineer
Dasarahalli Division
Bruhat Bangalore Mahanagara Palike
Dasarahalli Zone, Bangalore-57

Scanned by CamScanner

SNo	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Kumara BJ	
				In Figures (Rs)	In Words (Rs)
5	Proveding and Laying plain reinforced cement concrete for side drains using M 20 nominul mix concrete with OPC cement 300kgs. With 20mm and down size ganite metal course aggregates @0.69cum and fine aggregates @0.43cum machine mixed,well compacted for walls and bottom including centring,shuttring,cost of materails, HOM of machinaries. Complete Excluding cost of steel asper MORTH Specification no1500,1700,2200. Wall And Bottom thickness 15cm complete as per specifications and directions of engineer in charge of the work	cum	225.36	11800.00	Rupees Eleven Thousand and Eighty Hundred Only
6	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per pecifications.Specification No. KBS 4.6.3, TMT bars Fe 500. complete as per specifications and directions of engineer in charge of the work	Tonne	13.52	65000.00	Rupees Sixty Five Thousand Only
7	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications. and directions of engineer in charge of the work	sqm	471.75	1700.00	Rupees One Thousand and Seven Hundred anOnly

EXECUTIVE ENGINEER
Bru... ...anagara Palike,
Dasa...halli zone, Bangalore-57

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner